

# ROURKELA MUNICIPAL CORPORATION;ROURKELA

E-mail ID :- [rourkelamunicipality@gmail.com](mailto:rourkelamunicipality@gmail.com) Tele :- 0661-2500388 PIN :- 769012

No 8974 /Dt. 12.7.2017

## QUOTATION CALL NOTICE

Sealed quotations are invited from the intending Manufactures/Authorised dealers registered firms/Authorized licensed suppliers for supply, installation and commissioning of One 500LPH RO+UV automatic filter with chiller unit Water ATM in Rourkela Municipal Corporation area in Rourkela.

The bid should be accompanied with paper cost of Rs.2100.00 & EMD of Rs.10,000.00 in shape of DD/Bankers Cheque drawn in favour of Municipal Commissioner,RMC,copies of PAN,VAT clearance /GST number failing which the bid shall be rejected. The sealed bid should reach this office on or before **21.7.2017** 3.00PM by registered /speed post which will be opened on same date at 4.00pm in the chamber of Municipal Commissioner.

The detail Quotation Call Notice can be assessed from the website [www.rmc.nic.in](http://www.rmc.nic.in).

  
for  
Municipal Commissioner,  
Rourkela Municipal Corporation

Memo. No.8975

dated 12.7.2017

Copy to the Editor, Samaj, Odiya daily all circulation / Prameya Odiya Daily & Editor, The Telegraph , English daily with a request to publish the notice in their daily for one day on or before **13.7.2017** using minimum space & font size of "8".

  
for  
Municipal Commissioner,  
Rourkela Municipal Corporation

ROURKELA MUNICIPAL CORPORATION TENDER PAPER FOR Supply, installation and commissioning of One 500LPH RO+UV(Automatic filter ) with Chiller unit Water ATM .

SI No.	Item /Specification & Scope of work	Unit	Quantity	Rate in Rs.	Amount
1	2	3	4	5	6
1	<p>Supply, installation and commissioning of One 500LPH RO+UV(Automatic filter or equivalent) with Chiller unit Water ATM with following specification .</p> <p><b>STURCTURE</b> ;a .Decorative wall panels b. Anti corrosion treated MS Structure c. Continuous MIIG welded structure d. Stainless Steel shelf for water dispensing e. Door with lock for easy access and maintenance with in built ladder to reach overhead tank f. Adequate Steel dispenser and cladding g. Card/Coin system to programme 200ml,1Lt., 5Lt.</p> <p><b>Water processing Facility</b> ;a. 250/500 LPH RO Units. b. Water source – Bore water/PH Service Water c. Raw Water quality – TDS &lt; 3000PPM D. End product Quality –TDS &lt;100PPM e. Total suspended Solid removal f. Electric load -3 KW, g.Code Compliance –ISI10500 h. Automated unit to control operation ,i. UPVC piping j. Integrated UV system.</p> <p>Water Storage; 1000Ltr HDPE tank for Raw water storage and 300 Ltr - 400 Ltr tank for clean water.In case of raw water 24x7 ,1300 Ltr to 1500Ltr is used for clean water storage.</p> <p>Civil Work; Complete installation at levelled ground with 1 ft deep plinth.1.5 ft wide and 6 inch high brick platform with tiles fitting provision around the unit.</p> <p>Remote Monitoring System; Unit system should have microprocessor based Control Panels and in built modem to transfer data through SMS. The modem should be configured to suit SIM card of any Telecom Service Provider. It will send status and trip alerts to monitor the plant remotely. The SMS frequency and mobile numbers should be user settable. The modem should send plant status on Conductivity/TDS of product water, RO Permeate Flow Rate, RO inlet flow rate ,RO Permeate Volume, Membranes inlet and Outlet Pressures ,feed pump Current, Current and voltage Status, Plant status, RO operation Hour.</p> <p>Automatic system ; The automatic system will sense the water shortage in clean water tank and start the pump for drawing water from raw water storage tank. This will sequentially start the RO unit with pre-programmed logic. : The supply, erection, installation and commissioning with all taxes, transportation etc. with 1 year consumables , one year warranty with attend to all calls during the period.</p> <p>Liasioning with concerned authorities such as WESCO,PH and other electric &amp;PH connection &amp;other permissions</p>	each	1	all inclusive charges	Rs. all inclusive charges
	<b>Total Rs</b>				

Rates quoted must be inclusive of all taxes ,royalty, loading, unloading, transportation &all such incidental expenses.

In words Rupees

  
Municipal Commissioner ,  
Rourkela Municipal Corporation

Full signature of Quotationer.

## Term & Condition

1. **(a) Experience**  
The manufacturer, dealer, agency must have successfully installed one or more such ATMs .Documentary evidence must be submitted along with the bid.
2. **Time Period;**  
The work must be completed within 30 days failing which penalty@ ½% per day shall be levied maximum up to 10% of the value.
3. **Rates**  
The offer should be inclusive of all taxes, royalty, loading, unloading ,transit etc.
4. **Inspection**  
Before installation, the material must be inspected & approved by RMC authority. If any discrepancy or substandard material is noticed , the same has to be replaced without any extra cost.
5. All the civil works ,PH installation, fittings etc will be done as per supervision of by the EIC of RMC
6. As per site conditions deviation of required items if any shall be borne by the agency.
7. After installation of all fittings ,fixtures and commissioning of the Water ATM unit all complete the same will be considered as completed block or unit as the case may be.
8. Agency should submit warranty for a period of Twelve month .During the Warranty period the agency shall repair, restore or make good of the defects etc . of the materials/items by the agency.
9. The payment will be made to the supplier as follows ;
  - i) 90 % after successful commissioning ,testing &operation balance 10 % after performance of One year.
10. In case of any dispute, it will be resolved under jurisdiction of Rourkela only.

Signature of Quotationer

  
Municipal Commissioner ,  
Rourkela Municipal Corporation.